Paint Group Contractor Induction

Oct 13, 2026 · @Tom

The induction turns onboarding into a signed-off session where new contractors watch each step on the big screen, do it on their phone in the demo property, and tick it off. Thirteen short modules, about three hours with a break, in the contractor's own language.

How the induction runs

Every module has the same shape: three to five slides on the big screen, then "On your phone" in the demo property, then a short read-and-confirm block in their own language, then a tick in the app. Painters learn by doing, so nobody reads a document.

Who runs it	Tom or the Project Coordinator, in person, one to three new contractors at a time
Where	Big screen for the slides, each contractor on their own phone, Wi-Fi
How long	About three hours with one break. Can split into two sessions: modules 1 to 9, then 10 to 13
Language	The contractor picks their language on the first screen: English, Dari (Afghan), Farsi, Arabic (Lebanese), Spanish, Portuguese (Brazil) or Italian. The wording they read and tick to confirm understanding is in that language, including the standards. The slides, the app and the demo job stay in English
Paid	No. The invite says so, so nobody asks on the day
The demo property	12 Demo Street, a copy on every contractor's account. Same property, same planted events, so the slides always match the phone. Nothing in it counts toward their light or their money. "Reset demo" puts it back to the start
The check	No written test. Before they leave, the facilitator watches each contractor do five things without help: accept a job, add a before photo, move a surface to prepped, raise a variation, submit an invoice

The kit (facilitator only)	Roll of painter's tape, the laminated site card, and a sample board if one exists. The board is never mentioned on the slides

Slide rules. One idea per slide. Short sentences. A picture wherever a picture will do. Every module ends with an "On your phone" slide that names the exact taps, numbered, in the order the demo expects them. Say "Paint Group" or "your Project Coordinator", never a person's name.

The 13 modules in full

Each module below is written out as it runs on the day. **Slides** is what is on the big screen and what the facilitator says. **On your phone** is the exact taps in 12 Demo Street and what the contractor sees happen. **Check** is one question for the room before the tick. **Read and confirm** is the block the contractor reads in the app, in their own language, and ticks: it is the only part that is translated. **Tick** is the one-line statement that ends the module. **Worker version** says what changes when the module is run for workers.

Module 1 · Welcome and your account (10 min)

The contractor leaves this module with a working account, their language chosen, and a clear list of what we still need from them.

Slides

#	On the screen	What to say
1	**Welcome to Paint Group.** We find the work, quote it and look after the customer. You paint it to our standard. Three promises on every job: the customer always knows what is happening · the home is left clean · no surprises on price.	"Thanks for coming. Today is about how we work together, so your first job runs smoothly. We find the customers and handle the money. You do the painting. Three promises matter to us on every job: the customer always knows what is happening, the home is left clean, and there are no surprises on price. Everything today comes back to those three."
2	**How today works.** Slides on the screen. You do each step on your phone, in a practice job called 12 Demo Street. Tick each module when you have done it. About three hours, one break.	"You will not read a document today. You watch, then you do it on your phone. Nothing you do in 12 Demo Street is real. It is a practice job, so make your mistakes here, not on a customer's job."

#	On the screen	What to say
3	**What we need from you.** Public liability insurance · WorkCover if you have more than one worker · ABN and GST status · bank details · how many painters you bring.	"We need these before we can offer you a job. Insurance is the one we cannot work around."
4	**Haven't got your certificates with you?** That is fine today. The app shows what is missing and reminds you. Job offers start once your insurance is in.	"Don't worry if you haven't got them with you. Upload them from home tonight. The app will remind you until they are in."
5	**Choose your language.** What you read and tick to confirm is in your language, including the standards. The app and the demo job stay in English, with short words and pictures.	"Pick the language you read best. Everything you have to confirm today appears in that language. The app itself is in English, because the customer and the office use it in English, but the words are short and there are pictures."

On your phone

1. Open the link in your invite text. Choose your language. Everything you read and tick from now on is in that language.
2. Fill in your details: name, mobile, ABN, GST yes or no, bank details, and the number of painters you bring.
3. Upload your public liability certificate if you have it. If not, tap "I will add this later". It shows as **Missing** on your home screen until you add it.
4. Look at your home screen. 12 Demo Street is waiting there. Do not open it yet.

Check. Ask the room: what happens if you do not have your insurance yet? (You finish today. Job offers start when it is in.)

Read and confirm (in the contractor's language)

- I have given Paint Group my ABN, my GST status and my bank details.
- I will upload my public liability insurance before my first job. Job offers start when it is in.
- If I bring more than one worker, I need WorkCover.
- I understand the induction day is unpaid.
- I understand that 12 Demo Street is a practice job and nothing in it is real.

Tick: I have set up my account.

Worker version. Not in the worker induction. Workers are added by their contractor (Module 10) and choose their language the first time they log in.

Module 2 · How a Paint Group job runs (10 min)

The contractor can name the nine steps of a job and knows which ones are theirs.

Slides

#	On the screen	What to say
1	**One picture, nine steps.** Offer → Accept → Pre-start (colours, materials) → Work days (updates in the app) → Pre-defect → Walk-through with the customer → Sign-off → Invoice → Paid. Drawn as one line, with your steps marked.	"Every job follows these nine steps, in this order. The app shows you which step the job is on. Learn the names. We use them in every message we send you."
2	**Who does what.** Paint Group: quotes, books, orders materials, talks to the customer, pays you. You: accept, paint, update the app, check your own work, run the walk-through.	"The split is simple. We do the customer and the money. You do the painting and the app. If you are ever not sure whose job something is, it is ours. Ask."
3	**The walk-through is booked when you accept.** It is on the last day of the job. If the finish date changes, log it in the app the day you know, so we can tell the customer.	"The customer gets the walk-through date the moment you accept. If you are going to finish early or late, the customer needs to know before the day, not on it. You log it. We tell them."
4	**Your home screen.** Your jobs · your status light · your documents · the Standards tab. 12 Demo Street is your practice job.	"Open the app now. Everything you need on a job is on this one screen."

On your phone

1. Open 12 Demo Street from your home screen.
2. Find the nine steps at the top of the job. The job is on **Offer**, and the step you are on is highlighted.
3. Tap the Standards tab, look at the list of surfaces, then come back to the job. You will use it in Module 5.

Check. Ask the room: which step comes straight after the walk-through? (Sign-off.) Who books the walk-through? (Paint Group, the moment you accept.)

Read and confirm (in the contractor's language)

- A job has nine steps: Offer, Accept, Pre-start, Work days, Pre-defect, Walk-through, Sign-off, Invoice, Paid.
- Paint Group quotes the job, books it, orders the materials, talks to the customer and pays me.
- I accept the job, paint it, update the app, check my own work and run the walk-through.
- The walk-through is booked for the last day when I accept. If my finish date changes, I log it in the app the day I know.

Tick: I know the nine steps of a job.

Worker version. Same slides. On the phone: open the demo job and find the nine steps. Read and confirm: the first line and "My contractor accepts the job, raises variations and invoices. I paint, take photos and tick my surfaces."

Module 3 · In a customer's home (15 min)

These are the house rules. Most complaints come from behaviour, not paint.

Slides

#	On the screen	What to say
1	**You are a guest in someone's home.** How you behave is half of what the customer remembers.	"The customer will not remember your cutting-in. They will remember whether you were polite, clean and on time."
2	**Before you start.** Shoes off until the floors are covered. Cover every floor fully. On hard floors, use the floor protection we provide and tape the edges to seal the area. Ask: where to park, where to leave materials, may I use the toilet, power and water.	"Ask these questions on day one, before you bring anything in. Asking is respect. Guessing is a complaint."
3	**While you work.** No smoking, no drugs, no alcohol. No eating inside an occupied home. Music only if the customer is happy, and ask first. Keep pets and children away from wet paint and ladders. Don't move valuables: ask the customer to.	"Eat outside or in your van. Not sure if music is OK? Then no music. If something valuable is in the way, the customer moves it, not you. If it breaks in your hands, it is your problem."

#	On the screen	What to say
4	**Every day at the end.** Materials packed in the agreed place and covered neatly. Rubbish in one place, never scattered. Floors stay protected until the last coat is dry. Wet-paint signs where needed. Doors and windows you opened for ventilation locked. Keys and alarm as agreed.	"The customer walks through their home every evening. What they see at 6 pm is what they tell their friends. Ten minutes of packing up buys you a happy customer."
5	**Never.** Wash brushes in the customer's sink or garden (agree a place). Take photos of the home except the work. Post anything online. Bring anyone who is not on your crew. Open a tin before checking the colour schedule.	"Photos of the work go in the app. Nothing else, nowhere else. The colour schedule is on the work order. Check it before every tin, every time."
6	**Arriving.** Arrive at the agreed time. If you cannot make it or will be late, tell Paint Group the day before. On the day, before 7:30 am. We tell the customer. Never leave the customer waiting with no message.	"You never need to ring the customer about lateness. You ring us, early, and we handle it. Silence is the one thing we cannot fix."

On your phone

1. Open the induction and find Module 3, In a customer's home.
2. Read the site rules one at a time, in your language. Tick each one.

Check. Ask the room: it is 7:10 am and your van will not start. What do you do? (Call Paint Group now, before 7:30.) Can you eat your lunch in the customer's kitchen? (No. Outside or in the van.)

Read and confirm (in the contractor's language) — the site rules

- I am a guest in the customer's home. I am polite, and I ask before I use anything.
- Shoes off until the floors are covered. I cover every floor fully and tape hard-floor protection at the edges.
- Before I start I ask: where to park, where to leave materials, and whether I may use the toilet, power and water.
- No smoking, drugs or alcohol. No eating inside an occupied home. Music only if the customer is happy, and I ask first.
- I keep pets and children away from wet paint and ladders. I do not move valuables. I ask the customer to.

- At the end of every day: materials packed and covered in the agreed place, rubbish in one place, wet-paint signs up, doors and windows I opened locked, keys and alarm as agreed.
- I never wash brushes in the customer's sink or garden. I never take photos of the home except the work. I never post anything online.
- I never bring anyone who is not on my crew.
- I check the colour schedule before I open a tin.
- If I cannot come or will be late, I tell Paint Group the day before, or before 7:30 am on the day. I never leave the customer waiting with no message.

Tick: I will follow the site rules in every home.

Worker version. Same slides, same ten statements. Every worker ticks the site rules in their own language.

Module 4 · Materials and equipment (10 min)

No job stops because something ran out, and nobody argues about who brings what.

Slides

#	On the screen	What to say
1	**We supply the paint and everything you use up.** Paint, filler, caulk, tape, drop sheets, floor protection, sandpaper, rollers and brushes.	"If it gets used up on the job, we supply it."
2	**You bring the tools.** Ladders, spray equipment, pots, trays, poles, sanding equipment, power tools. Anything you do not use up.	"If it goes home with you at the end of the job, you bring it."
3	**Where the materials are.** We deliver to site where we can. Where we cannot, we order to the nearest paint shop for you to collect. The work order shows which.	"Check the Materials section of the work order the day before you start. It tells you if the paint is on site or waiting at the shop, and which shop."
4	**Short of something?** Tell us in the app or call. We order more. Never leave a job waiting because something ran out.	"Running out is normal. Not telling us is not. Tap Request more the moment you see you will be short, not the morning you need it."

#	On the screen	What to say
5	**Colour matches.** We arrange them before the job where we can. Sometimes we need you to go to the paint shop. We set it up first, so the right materials are ordered for the agreed scope.	"Never match a colour yourself without talking to us. The customer approved a colour. We need to be sure it is that one."
6	**Loan gear.** Where we have it, we lend spray equipment, big ladders and scaffold. Collect it and return it in the same condition.	"Loan gear comes back clean and working, the same as you got it. If something breaks, tell us the same day."

On your phone

1. On 12 Demo Street, tap **Materials**. It lists the paint and sundries for the job and where they are: Delivered to site, Thursday.
2. Tap **Request more** on one item. Pick a quantity. Send. A reply comes back from the Project Coordinator in a few seconds: "Ordered. At the paint shop tomorrow from 7 am."

Check. Ask the room: who brings the drop sheets? (Paint Group.) Who brings the pole? (You.)

Read and confirm (in the contractor's language)

- Paint Group supplies the paint and everything I use up: filler, caulk, tape, drop sheets, floor protection, sandpaper, rollers and brushes.
- I bring my tools: ladders, spray equipment, pots, trays, poles, sanding equipment and power tools.
- Materials are delivered to site where possible, otherwise ordered to the nearest paint shop. The work order shows which.
- If I am short of something, I request more in the app or I call. I never leave a job waiting.
- I do not arrange colour matches myself. Paint Group sets them up first.
- Loan gear goes back in the same condition I got it.

Tick: I know what we supply and what I bring.

Worker version. Same slides. On the phone: open Materials on the demo job and see where the paint is. Workers do not request materials; they tell their contractor when something is short. Read and confirm: the first two lines, plus "If something is running out, I tell my contractor straight away."

Module 5 · Finish standards (20 min)

This module is the approved painter guide, Finish Standards Version 1, taught one section at a time. The six ticks here are the standards sign-off itself. The slides come from the existing standards deck.

Slides

#	On the screen	What to say
1	**The three levels.** Level 2: clean, tidy repaint. Repairs what is broken. Level 3: our standard finish. Fixes what a customer can see from 1.5 m. Level 4: premium finish. Fixes what a customer can see up close. The level is on your work order, for every surface.	"Most of our jobs are Level 3. The level tells you how much preparation to do and how fine the finish must be. It is on every surface of your work order. If it is not there, ask before you start."
2	**Where the customer judges your work.** Level 2: 3 m. Level 3: 1.5 m. Level 4: 0.5 m, arm's length. The customer has the final say. Our quality checks use the same distances.	"Stand at that distance and look. If you can see it, fix it. The customer will stand there too."
3	**How it is judged.** Face the surface. Normal light: daylight, or the room lights on. No torch. High areas from the floor.	"Nobody judges your ceiling from a ladder with a torch. From the floor, in normal light. That is how we check, and that is how you check."
4	**Rules for every job.** No drips or runs. No paint where it should not be. No paint on hardware: remove it or mask it. Protect first. Full cover. Clean finish. Clean site every day, and clean site at the end.	"These do not change with the level. A Level 2 job with a drip on the tiles is a fail. If you spill or drip, clean it straight away. If it will not come off, tell us the same day."
5	**Your time.** Standard preparation is in your hours: covering, scraping, filling, gap filling, sanding, priming filler and bare patches. Bogging, stain blocking and additional coats are extra time on the work order. Anything not allowed for is a variation.	"You are never paid extra for standard prep. You are paid extra for bog, stain block and extra coats, and the work order shows the hours. If you find something that needs them and it is not on the work order: stop, photos, variation. Module 8 covers that."

#	On the screen	What to say
6	**One surface at a time: walls at Level 3.** Fill every hole, dent, crack and mark you can see from 1.5 m. Sand filler flat with soft edges, and sand the whole wall. Remove old drips and lumps you can see from 1.5 m. Lines sharp and straight from 1.5 m. Full, even cover: no patchy areas, no roller lines, no missed spots. Then the same slide for doors, then window frames.	"Every surface has its own list in the app, at every level. The list is the rule. Open it on the job and work down it. We will do three surfaces here. You read the rest on your phone."

On your phone

1. Open the induction and find Module 5, Finish standards. Read and tick each of the six sections: The three levels · Rules for every job · Your time · Interior surfaces · Exterior surfaces · The defect rule. Each section is in your language. The tick is at the end of each one.
2. Open 12 Demo Street, tap **Walls**, tap **What we expect**. This is the Level 3 list for walls, the same one you just saw on the screen.
3. Stand 1.5 m from the nearest wall in the room and do the look test. What can you see from there? That is what you would fix on a Level 3 job.

Check. Ask the room: the work order says Level 3 and there is an old drip you can only see from 30 cm. Do you fix it? (No. It cannot be seen from 1.5 m.) The same drip on a Level 4 job? (Yes.)

Read and confirm (in the contractor's language) — the six sections of Finish Standards Version 1, each with its own tick

Section	What it covers
The three levels	What Level 2, 3 and 4 mean, and the look test at 3 m, 1.5 m and 0.5 m
Rules for every job	Drips, paint in the wrong place, hardware, protect first, full cover, clean finish, clean site
Your time	What standard preparation includes, what earns extra time (bogging, stain blocking, additional coats), and the variation steps
Interior surfaces	The list for walls, ceilings, cornices, skirting boards, architraves, window frames and doors at each level

Section	What it covers
Exterior surfaces	The list for weatherboards, brick, render, picket fences, windows, doors, fascias, eaves, strapping and fretwork at each level
The defect rule	Find and fix your own defects before the customer sees them; the tape check on jobs of 16 hours or more

The wording the contractor reads is the standards guide itself, in the Standards tab. It is not repeated here.

Tick: the six standards ticks, one per section.

Worker version. Same slides, same six ticks, in the worker's language. Every painter on a Paint Group job signs the standards.

Module 6 · Quality checks and your status light (15 min)

The contractor knows what a clean job is, what each colour means, and that this is a reward system, not a fine.

Slides

#	On the screen	What to say
1	**What a clean job is.** The app kept up to date, from the reminder prompts. Every quality check passed first time. No call back in the 7 days after sign-off.	"Three things, and all three are in your hands. A job counts as clean seven days after sign-off."
2	**Who gets checked.** New painters: the first 3 jobs. Yellow: 1 job in 3. Orange: every job. Green: only when we choose.	"A quality check is your Project Coordinator looking at the job with the same look test you use. Pass first time and it counts for you. A fail you fix the same day is still a failed check, but it is not a call back."
3	**The five colours.** New (blue), Green, Yellow, Orange, Red. Four clean jobs in a row take you to Green. After that, your last ten jobs decide your colour. Jobs under 16 hours do not count.	"You start on New. Four clean jobs in a row and you are Green. After that, your last ten jobs decide your colour. Small jobs, under 16 hours, are not scored either way."

#	On the screen	What to say
4	**What each colour gets you.** Green: priority on new jobs, paid within 3 business days of sign-off, bonus eligible. Yellow: normal offers, normal payment. Orange: offers after Green and Yellow, a check on every job, a call from your Project Coordinator. **Red: no more job offers. We meet with you to go through the level of finish expected on your current job.**	"Green is where everyone should be, and the money shows it: paid in three business days. Red means we stop offering you work until we have met and gone through the finish on your current job. Jobs already in progress finish."
5	**Lost it? Win it back.** Four clean jobs in a row take you back to Green, from any colour.	"No colour is permanent. Four clean jobs, from anywhere, and you are Green again."
6	**This is a reward system.** It never takes money off your payment.	"Nothing here is a fine. Green gets you more. The other colours only change how closely we look and how we offer work."

On your phone

1. Tap the light on your home screen. It shows **New, 0 of 4**, and the four steps to Green.
2. A real text arrives now, marked DEMO: "DEMO: Please update your job in the app today." Tap the link. Add a photo to 12 Demo Street. The prompt shows as answered.
3. Tap **How the colours work** and read it. Then tap **What to do next**. The tips come from your own score.

Check. Ask the room: what three things make a clean job? How many clean jobs in a row to get to Green? (Four.) What does Red mean? (No more offers until we have met about the finish on the current job.)

Read and confirm (in the contractor's language)

- A clean job is: the app kept up to date from the reminder prompts, every quality check passed first time, and no call back in the 7 days after sign-off.
- When a reminder prompt arrives, I update the job that day.
- I start on New. Four clean jobs in a row take me to Green. After that, my last ten jobs decide my colour.
- Green: priority on new jobs, paid within 3 business days of sign-off, bonus eligible. Yellow: normal. Orange: offers after Green and Yellow, a check on every job, a call from my Project Coordinator. Red: no more job offers. We meet to go through the level of finish expected on my current job.

- Four clean jobs in a row take me back to Green from any colour.
- The status light is a reward system. It never takes money off my payment.

Tick: I understand how my status works and what Red means.

Worker version. Slides 1 and 2 only, retitled "What a clean job is and what counts". Workers have no light of their own. Their work counts toward their contractor's light. No DEMO text. Read and confirm: the first two lines, plus "My work counts toward my contractor's status light."

Module 7 · Talking to the customer (15 min)

Most disputes start with a painter answering a question that belonged to Paint Group.

Slides

#	On the screen	What to say
1	**Who talks about what.** You: hello on day one, what is happening today, simple questions about today's work, keep the site clean, update the app. Paint Group: price, scope, the level of finish, variations, colour changes, dates and walk-through bookings, complaints, call backs, invoices, customers who are not judging the work fairly, customers who need more reassurance, requests for extras outside the scope.	"Your side of the list is short on purpose. Everything else you pass to us. Not because we do not trust you. Because one voice on price and scope means no surprises for anyone."
2	**What the customer hears at each stage.** Booked: we confirm the dates. Day one: you say hello and explain the plan for the day. Work days: your app updates become their progress updates. Finish date change: you log it, we tell them. Last day: the walk-through. After: we send the invoice and the report.	"Your app updates go to the customer as progress. Every photo and every tick is a message to them. That is why keeping the app up to date matters so much."
3	**Running late or can't come.** Tell Paint Group the day before. On the day, before 7:30 am. We tell the customer. Never silence.	"Same rule as Module 3. It matters enough to say twice."

#	On the screen	What to say
4	**Finish date changing?** Log it in the app the day you know. We update the customer and the walk-through booking.	"Early is a change too. A customer who planned to be home on Friday does not want the walk-through on Wednesday with no warning."
5	**When a customer is unhappy.** 1 Stay calm and polite. Do not argue. 2 Listen. Let them finish. 3 Look at the area together, from the right distance for the level. 4 Fix it now if it is our standard and quick. 5 Anything else: no promises. Take photos and note it in the app. 6 Call Paint Group the same day. We take it from there.	"Six steps. The only hard one is not arguing. Look at it together from the right distance. Most of the time that settles it. If it does not, you are not the one who settles it. We are."
6	**Small extras are encouraged.** Never agree a price, a big extra or a change of scope on site. Say: "Good question. I will ask Paint Group to call you today."	"A small extra, five minutes, no materials: do it. It makes the customer happy. Anything bigger, that sentence. Learn it word for word."

On your phone

1. On 12 Demo Street, tap **Ask a question**. Type anything, for example "Which white for the ceiling?" Send. A reply comes back from the Project Coordinator in a few seconds, attached to the job.
2. Tap **Change finish date**. Pick a day later this week. Give a reason: "Extra prep in the hallway". Save. It shows as logged. On a real job the customer is told and the walk-through is moved.

Check. Ask the room: the customer asks what a second colour in the bedroom would cost. What do you say? ("Good question. I will ask Paint Group to call you today.")

Read and confirm (in the contractor's language)

- I say hello on day one and explain today's work. I answer simple questions about today's work. I keep the site clean and I update the app.
- I pass everything else to Paint Group: price, scope, the level of finish, variations, colour changes, dates, complaints, call backs and invoices.
- If I will be late or cannot come, I tell Paint Group the day before, or before 7:30 am on the day.
- If my finish date changes, I log it in the app the day I know.
- If a customer is unhappy: I stay calm, I listen, and we look at the area together from the right distance. I fix it now if it is our standard and quick. Anything else: no promises, photos, a note in the app, and I call Paint Group the same day.

- I never agree a price, a big extra or a change of scope on site. I say: "Good question. I will ask Paint Group to call you today."

Tick: I know what I say to the customer and what Paint Group says.

Worker version. Same slides, with "Paint Group" read as "my contractor or Paint Group". No phone steps: workers cannot ask a question or change a date in the app; they tell their contractor. Read and confirm: lines 1, 2, 5 and 6.

Module 8 · Variations (15 min)

A variation logged the moment it is seen gets paid. A variation raised at the end of the job starts an argument.

Slides

#	On the screen	What to say
1	**The scope is the job.** The work order lists every surface and the hours for it. Anything not itemised in the scope can be charged as a variation.	"Read the scope before day one. Walk the house with it on day one. What is on it, you paint. What is not on it is a question: not a freebie, and not a fight."
2	**Fair and reasonable.** Small items missed from the scope are part of the job, and what is small depends on the job. 2-day job: a missed window frame is a variation. 3-week job: 5 metres of fascia, or 1 door in 50, is expected. Do it. A whole room, a ceiling not in the scope, or a second colour is always a variation. Not sure? Ask before you start it.	"We do not use a number, because no number is fair on every job. Ask yourself: on a job this size, would a reasonable painter expect this to be included? If you are not sure, that is what Ask a question is for."
3	**Log it immediately.** The moment you see something missing or extra, log it. Not at the end of the job.	"A variation raised on day one gets priced and approved while you work. A variation raised on the last day cannot be approved before the walk-through, and the customer feels ambushed."
4	**The loop.** You log it with photos and hours → Paint Group prices it → the customer approves → it comes back to you to accept → it is added to your invoice. Never start the extra work before the customer has approved.	"Five steps, and you are in two of them: log, and accept. Everything in between is us and the customer. Do not start until it comes back approved."

#	On the screen	What to say
5	**What is never a variation.** Standard preparation. Paint applied too thin. Something you missed in your own work.	"Standard prep is in your hours. A third coat because the second was thin is on you. Bog, stain block and a real extra coat for a colour change are extra time. If they are not on the work order, that is a variation."

On your phone

1. On 12 Demo Street, find the extra door that is not in the scope. It is in the hallway. The scope lists three doors; there are four.
2. Tap **Raise a variation**. Pick **Extra item**. Add a photo. Enter 1.5 hours and a note: "Fourth door, hallway, not in scope". Send.
3. Watch it come back priced and approved. The demo customer approves it in a few seconds. Tap **Accept**. Open the invoice preview and see the line on it.

Check. Ask the room: a three-week exterior, and you find two metres of fascia not on the work order. Variation, or do it? (Do it.) A two-day interior, and a whole window frame is not on the work order? (Variation.)

Read and confirm (in the contractor's language)

- The work order is the scope. Anything not itemised in it can be a variation.
- Small items missed from the scope are part of the job. What is small depends on the job: on a long job a few metres of fascia or one door in fifty is expected; on a short job a missed window frame is a variation. A whole room, a ceiling not in the scope or a second colour is always a variation.
- I log a variation the moment I see it, with photos and hours. Not at the end of the job.
- I never start the extra work before the customer has approved it.
- Standard preparation, paint applied too thin and something I missed in my own work are never variations.
- Not sure? I ask before I start.

Tick: I know what a variation is and how to log one.

Worker version. Slides 1, 2 and 5, retitled "Variations: tell your boss, never agree extras". Workers do not raise variations. No phone steps. Read and confirm: "If I see something missing from the scope, or something extra, I tell my contractor straight away. I never agree an extra with the customer."

Module 9 · Pre-defect, walk-through and call backs (20 min)

The customer should find nothing. The painter who finds their own defects never gets a call back.

Slides

#	On the screen	What to say
1	**Why we pre-defect.** The customer should find nothing. Fewer defects at the walk-through. The customer sees we are one step ahead. You finish in one visit and do not come back.	"Every defect you find is one the customer does not. Every defect the customer finds costs you a return visit and costs us trust."
2	**The tape check (jobs of 16 hours or more).** Finish painting and clean the site. Walk the job on your own and do the look test on every surface. Put tape next to every defect. Fix each one and take the tape off. No tape left means ready.	"Walk it the way the customer will: room by room, from the right distance. The tape is for you. It stops you forgetting one. Under 16 hours you still check everything; you just do not need the tape."
3	**What counts as a defect.** Runs, drips, sags, missed spots, thin patches, old colour showing through, roller lines. Preparation not done to the level: holes, cracks and gaps not filled, filler not sanded flat. Wavy lines at ceilings, trim and glass. Paint on glass, hardware, floors, switches. Dust and hairs in the finish. Windows and doors stuck. Hardware not put back.	"This is the list your Project Coordinator uses on a quality check. Use the same one."
4	**Before the walk-through.** Site clean, rubbish gone, floors uncovered, hardware back, windows and doors open and close, final photos in the app.	"The customer should walk into a finished home, not a work site with good paint."
5	**How to walk the customer through.** Start at the front door. One room at a time. Let them look from the distance for the level. If they point at something small, fix it there and then. Anything bigger: note it in the app, no promises, Paint Group calls them. Then they sign on your phone.	"You lead the walk-through. Front door first, every room, let them look. A small mark, fix it in front of them. That is the best thing a customer can see. Something bigger: write it down, say we will call, and we do."

#	On the screen	What to say
6	**What a call back is.** A return visit on another day to fix workmanship. Fixed and signed the same day is a pass, not a call back. A customer call back counts for 7 days after sign-off. Only workmanship counts against you.	"A call back is not a punishment. It is a return visit. Fix it on the day and it is not one. Something the customer finds in the first week, we come back, and it counts. Something that is not your work, like a leak or damage after you left, does not count."

Do it in the room. The facilitator puts three pieces of tape on the wall. Each contractor finds them, says what they would fix, and takes the tape off.

On your phone

1. On 12 Demo Street, complete the finish checklist (eight ticks) and add a final photo.
2. Tap **Start walk-through**. The demo customer flags one area: "Mark on the hallway wall." Tap **Fixed**, add a photo, then walk again. The second walk comes back clean.
3. Sign the demo sign-off. The job moves to Sign-off, then to Invoice.

Check. Ask the room: the customer finds a drip at the walk-through, you fix it in ten minutes and they sign. Is that a call back? (No. Passed after a fix.) They ring three days later about a missed patch behind a door. (Yes. A call back, and it counts.)

Read and confirm (in the contractor's language)

- I find and fix my own defects before the customer sees them.
- On jobs of 16 hours or more I tape every defect, fix it, and take the tape off. No tape left means ready. On smaller jobs I still check every surface.
- Before the walk-through: site clean, rubbish gone, floors uncovered, hardware back, windows and doors open and close, final photos in the app.
- I lead the walk-through from the front door, one room at a time. Small things I fix there and then. Anything bigger: a note in the app, no promises, and Paint Group calls the customer.
- A call back is a return visit on another day to fix workmanship. It counts for 7 days after sign-off. Fixed and signed the same day is not a call back.

Tick: I check my own work before every walk-through.

Worker version. Same slides and the tape exercise in the room. No phone steps: the walk-through and sign-off belong to the contractor. Read and confirm: the first three lines.

Module 10 · The app day to day (20 min)

This is the module the reminder prompts and the customer's progress updates depend on.

Slides

#	On the screen	What to say
1	**A job offer lands.** It shows the address, the scope, the level, the hours and the money. Accept or decline within 24 hours. Accept means the dates are yours.	"Twenty-four hours. After that we offer it to someone else. Accept is a promise on the dates. Check your calendar before you tap."
2	**Share the job with your crew.** Add your workers in the app. Each worker gets a login, does the worker induction, and then sees the jobs you share: scope, standards, photos and ticks. Invoices, variations and messages stay with you.	"Your workers tick their own surfaces and add their own photos, under their own name. You cannot share a job with a worker who has not done the worker induction. Add them this week. We run worker sessions in groups."
3	**Before photos first.** One photo of each area before you touch it, in good light, the whole wall. The app will not let you start an area without one.	"Before photos protect you. A customer who says the wall was never cracked loses that argument in one tap."
4	**Stages.** Each surface goes To do → Prepped → Painted. Tick as you go. This is what the customer sees as progress.	"Tick it when you do it, from the room you are standing in. Not from the van at 5 pm, and never the next day."
5	**Keep it up to date.** Update on your first day, then every 2 to 3 days. We send reminder prompts. When a prompt comes in, update that day.	"This is what a clean job needs from you. A photo or a tick on the day the prompt arrives. Done."
6	**Not sure about something?** Ask in the app. It goes to your Project Coordinator with the job attached.	"Faster than a phone call, and the answer stays with the job."
7	**Rained off or no work today?** Tell Paint Group in the morning. We mark the day, and no prompt is sent.	"A day you do not work is not held against you, if we know. Tap it in the morning."

On your phone

1. Accept the 12 Demo Street offer. It moves to Accepted and the dates appear in your calendar.

2. Add a worker: name and mobile. Share the demo job with them. On a real job you can only share with a worker whose induction is complete. In the demo it goes through.
3. Add a before photo to Ceilings. Move Walls to Prepped, then to Painted. Each step shows a tick and a time.
4. Tap **No work today** and pick a reason. The day shows as marked.
5. Tap **Ask a question** if you did not in Module 7.

Check. Ask the room: a reminder text arrives at 7:30 am. What do you do, and by when? (A photo or a tick on that job, today.) Can your worker raise a variation? (No. Only you.)

Read and confirm (in the contractor's language)

- I accept or decline a job offer within 24 hours. Accepting means the dates are mine.
- My workers each have a login and do the worker induction before I share a job with them. Invoices, variations and messages stay with me.
- I take a before photo of each area before I touch it.
- I tick each surface as it moves from To do to Prepped to Painted, on the day.
- I update the app on my first day, then every 2 to 3 days, and on the day a reminder prompt arrives.
- If I have a question, I ask in the app. If I am not working on a booked day, I tell Paint Group in the morning.

Tick: I know how to run a job in the app.

Worker version. Slides 3, 4 and 5 only, retitled "Photos and stages". On the phone: open the demo job, add a before photo to Ceilings, move Walls to Prepped then Painted. Read and confirm: lines 3 and 4, plus "I tick my own work under my own name."

Module 11 · Money (10 min)

No haggling and no surprises: the price is fixed before you accept, and the invoice fills itself in.

Slides

#	On the screen	What to say
1	**Your price is on the offer.** Hours times the rate, fixed before you accept. Approved variations are added. No haggling, ever, with us or the customer.	"What you see on the offer is what you are paid, plus approved variations. Nobody negotiates on site, in either direction."

#	On the screen	What to say
2	**Invoice in the app.** After sign-off, tap Create invoice. It is already filled in from the job and the approved variations. Check it and submit.	"Two taps. If a line looks wrong, do not edit around it. Ask us before you submit."
3	**When you are paid.** Normal terms after sign-off. Green painters within 3 business days. A missing sign-off or missing before photos delays it.	"Green is paid in three business days. The two things that hold a payment up are a job with no customer sign-off, and a job with no before photos."
4	**Expenses.** Parking, a top-up of materials we asked you to buy, tip fees: photo of the receipt, amount, category, job. Over $100, ask first. Approved expenses go on your next payment at cost.	"Receipt photo, amount, pick the job. Over a hundred dollars, ask before you spend it."
5	**Bonuses.** Green painters are eligible. We tell you when one is added.	"That is all we say about bonuses today. Stay Green and you will hear from us."

On your phone

1. On 12 Demo Street, tap **Create invoice**. Check the variation from Module 8 is on it. Submit. It shows as Submitted. On a real job the office approves it and the due date appears.
2. Tap **Expenses** and add one: any photo, $20, Parking, 12 Demo Street. It shows as Pending approval.

Check. Ask the room: the customer offers you cash to do an extra room. What do you say? ("Good question. I will ask Paint Group to call you today.") What holds a payment up? (No sign-off, or no before photos.)

Read and confirm (in the contractor's language)

- My price is on the offer: hours times the rate, plus approved variations. I never haggle with Paint Group or with the customer.
- After sign-off I create the invoice in the app, check it and submit it.
- I am paid on normal terms after sign-off. Green painters are paid within 3 business days. A missing sign-off or missing before photos delays payment.
- I claim expenses with a receipt photo, the amount, the category and the job. Over $100, I ask first.

Tick: I know how to invoice and claim expenses.

Worker version. Not in the worker induction.

Module 12 · Calendar (5 min)

The calendar is how we offer work. An out-of-date calendar means offers you cannot take, and customers who lose their dates.

Slides

#	On the screen	What to say
1	**Your calendar is how we offer you work.** Keep it true. Block out days you cannot work before we book you, not after.	"We look at your calendar before we offer. A blocked day never gets an offer. A free day that you then cannot do costs a customer their dates."
2	**Link Google Calendar.** Your Paint Group jobs appear in your own calendar.	"One tap, and your jobs show up in the calendar you already use. It is one way: the app sends to Google. Changing something in Google does not change the job."

On your phone

1. Open **Calendar**. Block out next Friday. It shows as Unavailable.
2. Tap **Link Google Calendar** and sign in. 12 Demo Street appears in your Google Calendar within a minute.

Check. Ask the room: a family event lands on a day you are already booked. What do you do? (Tell Paint Group the day you know. Blocking the day in the calendar does not change a job already booked on it.)

Read and confirm (in the contractor's language)

- I keep my calendar true. I block out days I cannot work before Paint Group books me.
- Blocking a day does not change a job already booked on it. For that, I tell Paint Group straight away.
- My Paint Group jobs can show in my own Google Calendar. Changing them there does not change the job.

Tick: My calendar is up to date and linked.

Worker version. Not in the worker induction.

Module 13 · Safety basics (10 min)

Short, and it belongs in any induction. Nothing here replaces a white card.

Slides

#	On the screen	What to say
1	**Ladders and heights.** Footed, on a level base, three points of contact. Big ladders and scaffold: ask us, we lend them.	"Nobody falls off a ladder that is footed and level. Big ladders and scaffold are ours to lend, so there is never a reason to stretch."
2	**Old homes.** Houses built before 1970 may have lead paint. Sheet walls and eaves may be asbestos. If you think you have found either: stop, do not sand or scrape, call us.	"Powdery old paint on an old house, or flat grey sheeting with a dimpled pattern in the eaves: stop and ring. We get it tested. Nobody sands it until we know."
3	**Dust and fumes.** Sand with extraction or wet. Ventilate. Wet-paint signs where people walk.	"Windows open, extraction on, and signs up so the customer's kids do not walk into a wet door."
4	**Your crew.** You are responsible for everyone you bring. They work to the same rules, and your light covers all of them. Every worker needs a white card.	"Your worker's drip is your drip. Your worker's call back is your call back. Bring people you trust, and make sure they do the worker induction."
5	**Something unsafe at the home?** Exposed wiring, a dangerous roof, an aggressive dog: stop and call Paint Group before you continue.	"You are never expected to work through something unsafe. Stop, ring us, and we sort it out with the customer."

On your phone

1. Open the induction and find Module 13, Safety basics. Read the safety rules in your language and tick each one.

Check. Ask the room: you are scraping an eave on a 1960s house and the paint comes off as powder. What do you do? (Stop. Do not sand or scrape. Call Paint Group.)

Read and confirm (in the contractor's language) — the safety rules

- I use ladders footed, on a level base, with three points of contact. For big ladders and scaffold I ask Paint Group.
- If I think I have found lead paint or asbestos, I stop, I do not sand or scrape, and I call Paint Group.
- I sand with extraction or wet, I ventilate, and I put up wet-paint signs where people walk.
- I am responsible for everyone I bring. They work to the same rules. Every worker has a white card.

- If something at the home is unsafe, I stop and call Paint Group before I continue.

Tick: I will work safely and so will my crew.

Worker version. Same slides. Slide 4 becomes "Your contractor is responsible for you. You work to the same rules. You need a white card." Read and confirm: lines 1, 2, 3 and 5, plus "I have a white card."

Sign-off, the first three jobs, and the refresher

The sign-off

Each module ends with one tick, "I have done this and I understand it". Module 5 holds the six standards ticks. When every tick is in, the app records the induction as complete, with the date, the language and the version, and emails the contractor a PDF of what they confirmed. The practical check is recorded by the facilitator on their own screen: five tasks, pass or not yet.

Job offers start when: the induction is complete, the practical check is passed, and insurance is on file.

The first three jobs

1. **Day one of job one:** the Project Coordinator visits in the morning. Not a check, a hand-hold: photos, stages, where the materials are.
2. **Jobs one to three:** a quality check on each, as already ruled for new painters.
3. **After job three:** a 15-minute call. What was hard, what the app got wrong, what they would change.

The 60-minute refresher for existing contractors

Existing contractors do not sit the full induction. They do the refresher, in person or on a video call, and the same ticks.

Minutes	Module	Why
10	What is changing (standards, call backs, the light)	Sets the scene
10	Module 3 · In a customer's home	The rules are now written down
10	Module 7 · Talking to the customer	Who says what
10	Module 8 · Variations	Fair and reasonable, log it immediately

Minutes	Module	Why
10	Module 9 · Pre-defect and walk-through	The tape check
10	Module 6 · Your status light, plus the demo variation and walk-through on their phone	What Red means

They also read and tick the six standards sections, as already ruled. Materials, money and calendar are a one-page handout, not taught.

Keeping it current

When a rule changes in a material way, the changed module gets a "what changed" note and everyone re-ticks that module only. Small wording fixes do not trigger anything. Once a year, every contractor re-ticks the lot.

The worker induction

Every painter on a Paint Group job does an induction, so every worker gets a login. A worker login is small: their induction, the jobs their contractor shares with them, photos and surface ticks. Invoices, variations, messages and the status light stay with the contractor.

Who runs it	Paint Group, in group sessions. The contractor may sit in but does not sign for their workers
How long	About 90 minutes
Modules	2 How a job runs · 3 In a customer's home · 4 Materials · 5 Finish standards (the six ticks) · 6 What a clean job is and what counts (no light of their own) · 7 Talking to the customer · 8 Variations: tell your boss, never agree extras · 9 Pre-defect and walk-through · 10 Photos and stages only · 13 Safety
Not covered	Money, calendar, accepting offers, raising variations
The demo	Their own copy of 12 Demo Street with the worker steps only: open the job, add a before photo, move a surface to Prepped and Painted
The check	Three tasks without help: open the job, add a before photo, move a surface to Prepped

The gate	A contractor cannot put a worker on a job until that worker's induction is complete. PC Command shows who is not inducted

The worker's ticks are in their own language too.

The site card and the facilitator checklist

The laminated site card (one page, for the van)

Front: **In every home**

1. Shoes off until the floors are covered. Cover every floor. Tape hard-floor protection.
2. Ask first: parking, toilet, power, water, where materials go.
3. No smoking, drugs or alcohol. No eating inside an occupied home. Music only if the customer is happy.
4. Keep pets and children away from wet paint and ladders.
5. End of day: materials packed in the agreed place and covered, rubbish in one place, doors and windows locked, keys and alarm as agreed.
6. Never wash brushes in the sink or garden. Never post photos of a home.
7. Check the colour schedule before you open a tin.
8. Late or can't come? Tell Paint Group the day before, or before 7:30 am on the day.

Back: **Before the walk-through**

1. Look test on every surface, from the distance for the level.
2. Tape every defect. Fix. Tape off.
3. Site clean, floors uncovered, hardware back, windows and doors open and close.
4. Final photos in the app. Then walk the customer through, front door first.

Footer: **Paint Group · Questions: your Project Coordinator · Standards: the Standards tab in the app**

Facilitator checklist

Before the day

- Contractor's account created and the invite sent, with "the induction is unpaid" in the invite.
- 12 Demo Street is on their account. Open your own demo copy on the big screen and reset it.

- Phone with the DEMO text ready to send from the system.
- Kit: tape, site cards, sample board if there is one.

On the day

- Language chosen on each phone before Module 1.
- Run the modules in order. Do not skip the "On your phone" steps; they are the learning.
- Watch the progress screen. Nobody moves on until every phone has ticked.
- Module 9: the tape exercise on the wall.
- Practical check: the five tasks, without help, recorded on your screen.
- Hand over the site card.

After the day

- Confirm the induction shows complete and the PDF was emailed.
- Chase any missing certificates.
- Book the day-one visit for their first job.

For Tom: assumptions and open points

Everything you ruled on 13 October is in. These are the calls I made on top, and the few things still open. The read-and-confirm block in each module is my first-person wording of that module's rules. It is the only text that gets translated and ticked, so check those blocks most carefully.

Assumptions I made

- Job offers wait for insurance even though the induction continues without it.
- Module 10 says accept or decline an offer within 24 hours, which is the SLA already in the scheduling build.
- Module 11 says "over the threshold, ask first" for expenses, which is the $100 pre-approval rule in the cost-capture brief.
- Safety basics (Module 13) is my addition. It is short, but I think it belongs in any induction.
- The practical check is five tasks and the facilitator records pass or not yet. Nothing automated.
- The refresher covers modules 3, 6, 7, 8 and 9 plus the standards ticks. Materials, money and calendar become a one-page handout for existing contractors.
- Call backs are explained on the big screen only. The demo does not plant a call back on the contractor's own copy; it felt wrong to start their account with one.
- Re-tick once a year, and after any material change to a module.

Still open

- [ ] **Afghan language.** Afghanistan's main languages are Dari and Pashto. Dari is very close to Farsi, so one translation may serve both Afghan and Iranian painters. Confirm Dari, Pashto or both.
- [ ] **Translation method.** Settled: machine translation first, your team tests each language and sends back changes, and a language goes live only when you say. Only the tick wording is translated; the demo and the app stay English.
- [ ] **Materials threshold.** "Short of something" is fine, but who pays if a contractor runs out because of waste? Not stated anywhere yet.
- [ ] **Practical check fails.** If someone cannot do the five tasks, do they repeat the app modules the same day, or come back?
- [ ] **Day-one visit.** Is the Project Coordinator able to do this for every new contractor, or only the first few while numbers are small?

Next: the induction deck, built from these modules once you have read them and made your changes. The build brief is already with Claude Code.